



Division 5 Asbestos Assessment

**Broadmeadows Police Station
15 Dimboola Road
Broadmeadows, Victoria
Victoria Police
June 2020**

**Client No: V0014
Job No: 34511-039**

Table of Contents

Executive Summary.....	ii
Asbestos Building Materials Register.....	
NATA Endorsed Laboratory Sample Analysis Reports.....	
1 Introduction	1
2 Objective and Scope of Works	1
3 Site Description	1
4 Methodology.....	1
5 Findings	1
5.1 Assessment Findings	1
5.2 Areas not Accessed	2
6 Site Specific Recommendations	2
Risk Assessment Factors and Priority Ratings.....	
Statement of Limitations.....	

Executive Summary

Prensa Pty Ltd (Prensa) was engaged by Victoria Police to conduct a Division 5 Asbestos Assessment (Assessment) within the Broadmeadows Police Station located at 15 Dimboola Road, Broadmeadows, Victoria (the Site).

The following significant key findings are noted:

- ‘Low’ risk non-friable asbestos-containing materials were identified at the Site including mastic and fibre cement sheet.
- ‘Low’ risk friable asbestos-containing materials have been assumed to be present within the internal linings/insulation of the safe at the Site; and
- ‘Low’ risk non-friable asbestos-containing materials were assumed to be present at the Site including fuses and internal linings of filing cabinets.

Recommendations


The following key recommendations are provided for the management of asbestos-containing materials:

- An Asbestos Management Plan (AMP) should be created and maintained for all ACM that remain at the Site to assist the Site controller with the management of these materials. The AMP must ensure that suitable control measures are implemented to prevent Site personnel and others from being exposed to airborne asbestos fibre; and
- In accordance with the OHS Regulation 2017, a Division 6 Asbestos Assessment (intrusive works) should be undertaken prior to any demolition or refurbishment works. Any asbestos building materials identified within this survey should be removed prior to the commencement of any works that may cause disturbance - as per Australian Standard (AS) 2601:2001 *The Demolition of Structures*.


Recommendations for specific items of asbestos-containing building materials are also presented in **Attachment: Asbestos Building Materials Register** of this Assessment report. This executive summary must be read in conjunction with this entire report.

Asbestos Building Materials Register

KEY TO ASBESTOS-CONTAINING MATERIALS PRIORITY RISK RATING:		
Priority 1 (P1)		High Priority - Requiring immediate action
Priority 2 (P2)		Medium Priority – May require action in the short term
Priority 3 (P3)		Low Priority – May require action in the medium term
Priority 4 (P4)		Very Low Priority - Requires ongoing management or longer term remedial action

Client: Victoria Police		Site Address: Broadmeadows Police Station													Job No: 34511-039				
Area / Level	Room & Location	Feature	Item Description	Hazard Type	Hazard Status	Sample Number	Friability	Labelled Y/N	Source of Asbestos That is Not Fixed or Installed	Workplace Activities Likely to Disturb Asbestos	Disturb. Potential	Condition	Risk Status	Approx. Quantity	Control Priority	Comments & Recommendations	Date of Identification	Reinspect Date	Photograph
Ground floor	Main foyer	Floor	Vinyl sheet (cream)	Asbestos	Negative	34511-039-001	-	-	-	-	-	-	-	-	-	-	-	-	
Ground floor	Front desk area	Floor	Vinyl sheet (grey)	Asbestos	Negative	34511-039-002	-	-	-	-	-	-	-	-	-	-	-	-	
Ground floor	Front desk area	Filing cabinet	Internal lining	Asbestos	Assumed positive	-	Non-friable	Yes	-	None under normal occupation and use	Low	Good	Low	3 units	P4	Maintain in current condition if to remain in-situ. Remove under controlled bonded asbestos removal conditions prior to refurbishment or demolition works by a Class A (friable & non-friable) or Class B (non-friable) licensed asbestos removal contractor.	Apr-20	Apr-25	
Ground floor	Soft interview room No.2	Skirting board	Vinyl sheet (brown)	Asbestos	Negative	34511-039-003	-	-	-	-	-	-	-	-	-	-	-	-	
Ground floor	Kitchenette	Floor	Hessian back sheet vinyl (dark grey)	Asbestos	Negative	34511-039-004	-	-	-	-	-	-	-	-	-	-	-	-	
Ground floor	Corridor adjacent cells and custody counter	Floor	Vinyl sheet (cream)	Asbestos	Negative	Same as 34511-039-001	-	-	-	-	-	-	-	-	-	-	-	-	
Ground floor	Lift foyer	Floor	Vinyl sheet (cream)	Asbestos	Negative	Same as 34511-039-001	-	-	-	-	-	-	-	-	-	-	-	-	
First floor	Switch Room	Switchboard	Fuses	Asbestos	Assumed positive	-	Non-friable	Yes	-	None under normal occupation and use	Low	Good	Low	60	P4	Maintain in current condition if to remain in-situ. Remove under controlled bonded asbestos removal conditions prior to refurbishment or demolition works by a Class A (friable & non-friable) or Class B (non-friable) licensed asbestos removal contractor.	Apr-20	Apr-25	
First floor	Switch Room	Automatic battery charger	Fuses	Asbestos	Assumed positive	-	Non-friable	Yes	-	None under normal occupation and use	Low	Good	Low	12	P4	Maintain in current condition if to remain in-situ. Remove under controlled bonded asbestos removal conditions prior to refurbishment or demolition works by a Class A (friable & non-friable) or Class B (non-friable) licensed asbestos removal contractor.	Apr-20	Apr-25	
First floor	Ceiling space throughout	Ductwork	Flange mastic (brown)	Asbestos	Positive	34511-039-005	Non-friable	No	-	None under normal occupation and use	Low	Good	Low	Throughout	P4	Height restriction. Maintain in current condition if to remain in-situ. Remove under controlled bonded asbestos removal conditions prior to refurbishment or demolition works by a Class A (friable & non-friable) or Class B (non-friable) licensed asbestos removal contractor.	Apr-20	Apr-25	

Client: Victoria Police		Site Address: Broadmeadows Police Station													Job No: 34511-039				
Area / Level	Room & Location	Feature	Item Description	Hazard Type	Hazard Status	Sample Number	Friability	Labelled Y/N	Source of Asbestos That is Not Fixed or Installed	Workplace Activities Likely to Disturb Asbestos	Disturb. Potential	Condition	Risk Status	Approx. Quantity	Control Priority	Comments & Recommendations	Date of Identification	Reinspect Date	Photograph
First floor	Comms area	Floor	Vinyl floor tile (speckled)	Asbestos	Negative	34511-039-006	-	-	-	-	-	-	-	-	-	-	-	-	
First floor	Fan Room	Air handling unit ductwork	Flange mastic (grey)	Asbestos	Positive	34511-039-007	Non-friable	Yes	-	None under normal occupation and use	Low	Good	Low	Throughout	P4	Maintain in current condition if to remain in-situ. Remove under controlled bonded asbestos removal conditions prior to refurbishment or demolition works by a Class A (friable & non-friable) or Class B (non-friable) licensed asbestos removal contractor.	Apr-20	Apr-25	
First floor	Fan Room	Wall opposite AHU inlet	Fibre cement sheet infill panel	Asbestos	Positive	34511-039-008	Non-friable	Yes	-	None under normal occupation and use	Low	Good	Low	2m ²	P4	Maintain in current condition if to remain in-situ. Remove under controlled bonded asbestos removal conditions prior to refurbishment or demolition works by a Class A (friable & non-friable) or Class B (non-friable) licensed asbestos removal contractor.	Apr-20	Apr-25	
First floor	Male locker room	Floor	Vinyl sheet (beige)	Asbestos	Negative	34511-039-009	-	-	-	-	-	-	-	-	-	-	-	-	
First floor	Male locker room	Wall adjacent entrance to office	Vinyl sheet (black)	Asbestos	Negative	34511-039-010	-	-	-	-	-	-	-	-	-	-	-	-	
First floor	Male locker room	Throughout	Skirting vinyl sheet (brown)	Asbestos	Negative	Same as 34511-039-003	-	-	-	-	-	-	-	-	-	-	-	-	
First floor	Kitchen	Floor	Vinyl sheet (beige)	Asbestos	Negative	Same as 34511-039-009	-	-	-	-	-	-	-	-	-	-	-	-	
First floor	Kitchen	Wall	Skirting vinyl sheet (brown)	Asbestos	Negative	Same as 34511-039-003	-	-	-	-	-	-	-	-	-	-	-	-	
First floor	Fan Room 2.24	Air handling unit ductwork	Flange mastic (grey)	Asbestos	Positive	Same as 34511-039-007	Non-friable	Yes	-	None under normal occupation and use	Low	Good	Low	10 lm	P4	Maintain in current condition if to remain in-situ. Remove under controlled bonded asbestos removal conditions prior to refurbishment or demolition works by a Class A (friable & non-friable) or Class B (non-friable) licensed asbestos removal contractor.	Apr-20	Apr-25	
External	Fan Room	Brick wall	Construction joint mastic (brown)	Asbestos	Negative	34511-039-011	-	-	-	-	-	-	-	-	-	-	-	-	

Client: Victoria Police		Site Address: Broadmeadows Police Station														Job No: 34511-039			
Area / Level	Room & Location	Feature	Item Description	Hazard Type	Hazard Status	Sample Number	Friability	Labelled Y/N	Source of Asbestos That is Not Fixed or Installed	Workplace Activities Likely to Disturb Asbestos	Disturb. Potential	Condition	Risk Status	Approx. Quantity	Control Priority	Comments & Recommendations	Date of Identification	Reinspect Date	Photograph
External	Fan Room	Air handling unit ductwork	Flange mastic (grey)	Asbestos	Positive	Same as 34511-039-007	Non-friable	Yes	-	None under normal occupation and use	Low	Good	Low	10 lm	P4	Maintain in current condition if to remain in-situ. Remove under controlled bonded asbestos removal conditions prior to refurbishment or demolition works by a Class A (friable & non-friable) or Class B (non-friable) licensed asbestos removal contractor.	Apr-20	Apr-25	
External	Boiler Room	Switchboard	Fuses	Asbestos	Assumed positive	-	Non-friable	Yes	-	None under normal occupation and use	Low	Good	Low	1 m ²	P4	Confirm Status, label as containing asbestos and maintain in current condition if to remain in-situ, remove under controlled bonded asbestos removal conditions prior to refurbishment or demolition works by a Class A (friable & non-friable) or Class B (non-friable) licensed asbestos removal contractor.	Apr-20	Apr-25	
External	Boiler Room	Boiler pipework	Gasket (black)	Asbestos	Negative	34511-039-012	-	-	-	-	-	-	-	-	-	-	-	-	
External	Boiler Room	Boiler pipework	Gasket (orange)	Asbestos	Negative	34511-039-013	-	-	-	-	-	-	-	-	-	-	-	-	
External	Boiler Room	Wall	Construction joint mastic	Asbestos	Negative	34511-039-014	-	-	-	-	-	-	-	-	-	-	-	-	
External	East roof fan room	Walls throughout	Fibre cement sheet infill panel	Asbestos	Negative	34511-039-016	-	-	-	-	-	-	-	-	-	-	-	-	
External	Roof	East ductwork	Flange mastic (grey)	Asbestos	Positive	34511-039-015	Non-friable	Yes	-	None under normal occupation and use	Low	Good	Low	20 m ²	P4	Maintain in current condition if to remain in-situ. Remove under controlled bonded asbestos removal conditions prior to refurbishment or demolition works by a Class A (friable & non-friable) or Class B (non-friable) licensed asbestos removal contractor.	Apr-20	Apr-25	
External	East roof fan room	Ceiling	Fibre cement sheet infill panel	Asbestos	Negative	Same as 34511-039-016	-	-	-	-	-	-	-	-	-	-	-	-	
External	Brown walls throughout	Brown walls throughout	Construction joint mastic	Asbestos	Negative	Same as 34511-039-014	-	-	-	-	-	-	-	-	-	-	-	-	
Internal	Ground, property storage	Grey speckled floor	Vinyl sheet (grey speckled)	Asbestos	Negative	34511-039-017	-	-	-	-	-	-	-	-	-	-	-	-	

Client: Victoria Police			Site Address: Broadmeadows Police Station														Job No: 34511-039		
Area / Level	Room & Location	Feature	Item Description	Hazard Type	Hazard Status	Sample Number	Friability	Labelled Y/N	Source of Asbestos That is Not Fixed or Installed	Workplace Activities Likely to Disturb Asbestos	Disturb. Potential	Condition	Risk Status	Approx. Quantity	Control Priority	Comments & Recommendations	Date of Identification	Reinspect Date	Photograph
Ground floor	Lift foyer	Lift	Internal lining	-	-	-	-	-	-	-	-	-	-	-	-	No access at the time of the Assessment	-	Apr-25	
Ground floor	Main foyer	Room adjacent disabled toilet	-	-	-	-	-	-	-	-	-	-	-	-	-	No access due to locked door.	-	Apr-25	No photo available

NATA Endorsed Laboratory Sample Analysis Report

14 April 2020

Tom McDonald

Victoria Police

Level 10, Tower 3, 637 Flinders Street

Docklands VIC 3008

Dear Tom,

Asbestos Bulk Sample Analysis Report

Broadmeadows Police Station, 15 Dimboola Road, Broadmeadows VIC 3047

Please find attached the asbestos bulk sample analysis results of the 17 samples collected by Paul Sessarego of Prensa Pty Ltd for Broadmeadows Police Station, 15 Dimboola Road, Broadmeadows VIC 3047 on 8 April 2020 and received at the Prensa Pty Ltd laboratory (GF, 5 Burwood Rd, Hawthorn VIC 3122) on 8 April 2020. The samples were analysed on 14 April 2020 and the results are presented on the following page(s).

Prensa qualitatively analyses bulk samples for asbestos using polarising light microscopy and dispersion staining techniques in accordance with Prensa Test Method PRLAB2002 Asbestos Identification, and in accordance with Australian Standard (AS) 4964 – 2004, *Method for the qualitative identification of asbestos in bulk samples*.

If you require further information please contact the Prensa office on (03) 9508 0100.

Regards,



Hazirah Soffiee

Approved Asbestos Identifier and Signatory



GF, 5 Burwood Rd, Hawthorn VIC 3122 ABN: 12 142 106 581

Accredited for compliance with ISO/IEC 17025 - Testing. Corporate Site Number 19121. This document shall not be reproduced except in full. Sampling is not covered by the scope of the NATA accreditation.

Asbestos Bulk Sample Analysis Report

Broadmeadows Police Station, 15 Dimboola Road, Broadmeadows VIC 3047

Sample No	Sample Location / Description / Size	Result
34511 - 039 - 001	Internal, ground floor, main foyer, floor, cream sheet vinyl	No asbestos fibres detected
	Cream flexible vinyl material with attached yellow adhesive 50 x 20 x 5 mm	Organic fibres detected
34511 - 039 - 002	Internal, ground floor, front desk area, floor, grey sheet vinyl	No asbestos fibres detected
	Grey flexible vinyl material 40 x 20 x 5 mm	Organic fibres detected Synthetic Mineral Fibres detected
34511 - 039 - 003	Internal, ground floor, soft interview room 2, brown skirting vinyl	No asbestos fibres detected
	Brown flexible vinyl material 40 x 20 x 5 mm	
34511 - 039 - 004	Internal, ground floor, watchouts kitchen, floor, dark grey hessian blacked vinyl	No asbestos fibres detected
	Grey flexible vinyl material with attached yellow hessian backing material 30 x 10 x 5 mm	Organic fibres detected
34511 - 039 - 005	Internal, ceiling space, throughout, ductwork, flange, brown mastic	Chrysotile (white asbestos) detected
	Brown rubbery mastic material 20 x 10 x 5 mm	
34511 - 039 - 006	Internal, level 1, comms area, floor, speckled vinyl	No asbestos fibres detected
	Multi-coloured flexible vinyl material 20 x 15 x 5 mm	
34511 - 039 - 007	Internal, level 1, fan room, air handling unit, ductwork, grey flange mastic	Chrysotile (white asbestos) detected
	Grey rubbery mastic material 40 x 20 x 5 mm	
34511 - 039 - 008	Internal, level 1, fan room, wall opposite air handling unit, infill panel, fibre cement sheet	Chrysotile (white asbestos) detected
	Grey fibrous cement material 20 x 15 x 5 mm	Amosite (brown asbestos) detected
34511 - 039 - 009	Internal, level 1, male locker room, floor, beige vinyl	No asbestos fibres detected
	Beige brittle vinyl material with attached yellow adhesive 50 x 20 x 5 mm	
34511 - 039 - 010	Internal, level 1, male locker room, wall adjacent entry, black sheet vinyl	No asbestos fibres detected
	Black brittle vinyl material 30 x 30 x 5 mm	Organic fibres detected
34511 - 039 - 011	External, fan room, brick walls, brown construction joint mastic	No asbestos fibres detected
	Brown rubbery mastic material 30 x 10 x 5 mm	
34511 - 039 - 012	External, boiler room, boiler pipework, black gasket	No asbestos fibres detected
	Black gasket material 30 x 20 x 5 mm	Organic fibres detected

Asbestos Bulk Sample Analysis Report

Broadmeadows Police Station, 15 Dimboola Road, Broadmeadows VIC 3047

Sample No	Sample Location / Description / Size	Result
34511 - 039 - 013	External, boiler room, boiler pipework, orange gasket	No asbestos fibres detected
	Orange gasket material	Organic fibres detected
	20 x 10 x 5 mm	
34511 - 039 - 014	External, boiler room, brick walls, brown construction joint mastic	No asbestos fibres detected
	Brown rubbery mastic material	
	20 x 10 x 5 mm	
34511 - 039 - 015	External, roof, east end, blue ductwork, grey flange mastic	<i>Chrysotile (white asbestos) detected</i>
	Grey rubbery mastic material	
	15 x 10 x 5 mm	
34511 - 039 - 016	External, roof, east end fan room, wall, throughout, fibre cement sheet	No asbestos fibres detected
	Grey fibrous cement material	Organic fibres detected
	40 x 20 x 5 mm	
34511 - 039 - 017	Internal, ground floor, property storage, floor, grey speckled sheet vinyl	No asbestos fibres detected
	Grey flexible vinyl material	Synthetic Mineral Fibres detected
	40 x 20 x 5 mm	

Only the samples submitted for analysis have been considered in presenting these results.

1 Introduction

Prensa Pty Ltd (Prensa) was engaged by Victoria Police to conduct a Division 5 Asbestos Assessment (Assessment) within nominated areas of Broadmeadows Police Station located at 15 Dimboola Road, Broadmeadows, Victoria (the Site). A Prensa consultant conducted the Assessment on the 8th April 2020 at the request of Tom McDonald of Victoria Police.

2 Objective and Scope of Works

For the objective and scope of works relating to the undertaking of this Assessment please refer to Prensa report: *34511 Victoria Police Asbestos Audits*.

3 Site Description

The Site consists of a two (2) storey commercial building. Details of the building contained within this site are provided in **Table 1**.

Table 1: Site Information			
Site Address	15 Dimboola Road, Broadmeadows, Victoria		
Year of Construction Completion:	1985	External walls:	Brick
Approximate area:	6,272 m ²	Internal walls:	Plaster
Levels:	2	Ceiling:	Plaster
Roof type:	Metal	Floor and coverings:	Carpet, vinyl
Assessment Time:	During normal business hours	Site Occupation:	Occupied

4 Methodology

For methodology relating to the undertaking of this Assessment please refer to Prensa report: *34511 Victoria Police Asbestos Audits*. Where asbestos was found to exist a risk assessment was conducted on each item and a priority rating applied. This was conducted in accordance with the protocols described in **Attachment: Risk Assessment Factors and Priority Ratings**.

5 Findings

5.1 Assessment Findings

The findings of this Assessment are presented in tabulated format in **Attachment: Asbestos Building Materials Register** of this Assessment report. The Asbestos Bulk Sample Analysis Report is provided in **Attachment: NATA Endorsed Laboratory Sample Analysis Report**.

It is noted that asbestos was identified or assumed to be present during the Assessment.

5.2 Areas not Accessed

Areas that are generally not accessed as part of Prensa's Assessments are listed in Prensa report 34511 *Victoria Police Asbestos Audits*. Site-specific areas that were inaccessible during Prensa's Assessment and were deemed likely to contain asbestos are also listed in **Attachment: Asbestos Building Materials Register**.

6 Site Specific Recommendations

Based on the findings of this Assessment, it is recommended that the following control measures be adopted as part of the management of the asbestos-containing materials at the Site. Recommendations for specific items of asbestos-containing building materials are also presented in **Attachment: Asbestos Building Materials Register** of this Assessment report.

- An Asbestos Management Plan (AMP) should be created and maintained for all ACM that remain at the Site to assist the Site controller with the management of these materials. The AMP must ensure that suitable control measures are implemented to prevent Site personnel and others from being exposed to airborne asbestos fibre; and
- In accordance with the OHS Regulations, 2017 a Division 6 Asbestos Assessment (intrusive works) should be undertaken prior to any demolition or refurbishment works. Any asbestos building materials identified within this survey should be removed prior to the commencement of any works that may cause disturbance - as per Australian Standard (AS) 2601:2001 *The Demolition of Structures*.

Risk Assessment Factors and Priority Ratings

Risk Assessment Factors

To assess the health risk posed by the presence of ACM, all relevant factors must be considered. These factors include:

- Product type;
- Condition;
- Disturbance potential;
- Friability of the material;
- Proximity to direct air stream; and
- Surface treatment (if any).

The purpose of the material risk assessment is to establish the relative risk posed by specific ACM identified in this Assessment. The following risk factors are defined to assist in determining the relative health risk posed by each item.

Condition

The condition of the ACM identified during the Assessment is reported as being **good**, **fair** or **poor**.

- **Good** refers to a material that is in sound condition with no or very minor damage or deterioration.
- **Fair** refers to a material that is generally in a sound condition, with some areas of damage or deterioration.
- **Poor** refers to a material that is extensively damaged or deteriorated.

Friability

The friability of a material describes the ease by which the material can be crumbled, which in turn, can increase the release of fibres into the air.

- **Friable asbestos** can be crumbled, pulverised, or reduced to powder by hand pressure, which makes it more dangerous than non-friable asbestos.
- **Non-friable asbestos**, more commonly known as bonded asbestos, is typically comprised of asbestos fibres tightly bound in a non-asbestos matrix. If accidentally damaged or broken these ACM may release fibres initially but will not continue to do so.

Disturbance Potential

ACM can be classified as having low, medium or high disturbance potential.

- **Low disturbance potential** describes materials that have very little or no activity in the immediate area with the potential to disturb the material. Low accessibility is considered as monthly occupancy or less, or inaccessible due to its height or its enclosure.
- **Medium disturbance potential** describes materials that have moderate activity in the immediate area with the potential to disturb the material. Medium accessibility is considered weekly access or occupancy.
- **High disturbance potential** describes materials that have regular activity in the immediate area with the potential to disturb the material.

Health Risk Status

The risk factors described above are used to grade the potential health risk ranking posed by the presence of the materials. These risk rankings are described below:

- A **low health risk** describes a material that poses a negligible or low health risk to occupants of the area due to the materials not readily releasing fibres unless seriously disturbed.
- A **medium health risk** describes a material that pose a moderate health risk due to the material status and activity in the area.
- A **high health risk** describes a material that pose a high health risk to personnel or the public in the area of the material.

ACM Priority Rating System for Control Recommendations

While an Assessment of health risk has been made, our recommendations have been prioritised based on the practicability of a required remedial action. In determining a suitable priority ranking, consideration has been given to the following:

- Level of health risk posed by the asbestos containing material;
- Potential commercial implications of the finding; and
- Ease of remediation.

As a guide the recommendation priorities have been given a timeframe as follows:

P1

**High Risk
Requiring
Immediate
Action**

Status: ACM which are either damaged or are being exposed to continual disturbance. Due to these conditions there is an increased potential for exposure and/or transfer of the material to other parts of the property if unrestricted use of the area containing the material is allowed.

Recommendation: If the ACM is in a poor/unstable condition and accessible with risk to health from exposure, immediate access restrictions to the immediate area should be applied, air monitoring should be considered and removal is recommended as soon as practicable using an appropriately licensed asbestos removalist.

P2

**Medium Risk
Requiring
Action in
Short Term**

Status: ACM with a potential for disturbance due to the following conditions:

- Material has been disturbed or damaged and in its current condition, while not posing an immediate risk, is unstable.
- The material is accessible and can, when disturbed, present a short-term exposure risk.
- The material could pose an exposure risk if workers are in close proximity.

Recommendation: If the ACM are easily accessible but in a stable condition, removal is preferred. Nevertheless, if removal is not immediately practicable, short-term control measures (i.e. restrict access, sealing, enclosure etc.) may be employed until removal can be facilitated as soon as is practicable.

P3

Low Risk
Requiring
Action in
Medium-
Term

Status: ACM with a low potential for disturbance due to the following conditions:

- The condition of any friable asbestos-containing building material is stable and has a low potential for disturbance i.e. is encased in metal cladding.
- The ACM is in a non-friable condition, however further disturbance or damage is unlikely other than during maintenance or service and does not present an exposure risk unless cut, drilled, sanded or otherwise abraded.

Recommendation: There are low health risks if the material is left undisturbed under the control of an asbestos management plan. The site controller should consider organising the removal or encapsulation of the damaged non-friable ACM. These ACM should be left in a good and stable condition, with ongoing maintenance and periodic inspection if they are to

P4

**Negligible
(Very Low)
Risk**
Requiring
Ongoing
Management
or Extended
Remedial
Action

Status: ACM of a non-friable form and in good condition. It is unlikely that the material can be disturbed under normal circumstances. Even if it were subjected to minor disturbance the asbestos-containing material poses a low health risk.

Recommendation: These ACM should be maintained in a good and stable condition, with ongoing maintenance and periodic inspection in line with current state legislation. It is advisable that any remaining identified or assumed ACM should be appropriately labelled (with a warning against disturbing the materials), where possible, and regularly inspected to ensure they are not deteriorating resulting in a potential risk to health.

Statement of Limitations

This document has been prepared in response to specific instructions from Victoria Police to whom the report has been addressed. The work has been undertaken with the usual care and thoroughness of the consulting profession. The work is based on generally accepted standards and practices of the time the work was undertaken. No other warranty, expressed or implied, is made as to the professional advice included in this report.

The report has been prepared for the use by Victoria Police and the use of this report by other parties may lead to misinterpretation of the issues contained in this report. To avoid misuse of this report, Prensa advises that the report should only be relied upon by Victoria Police and those parties expressly referred to in the introduction of the report. The report should not be separated or reproduced in part and Prensa should be retained to assist other professionals who may be affected by the issues addressed in this report to ensure the report is not misused in any way.

Unless otherwise stated in this report, the scope is limited to fixed and installed materials and excludes buried waste materials, contaminated dusts and soils.

Unless expressly stated it is not intended that this report be used for the purposes of tendering works. Where this is the intention of Victoria Police, this intention needs to be communicated with Prensa and included in the scope of the Proposal.

Prensa is not a professional quantity surveyor (QS) organisation. Any areas, volumes, tonnages or any other quantities noted in this report are indicative estimates only. The services of a professional QS organisation should be engaged if quantities are to be relied upon.

Sampling Risks

It is noted that while the assessment has attempted to locate the asbestos-containing materials within the building(s), the investigation was limited to only a visual assessment and limited sampling program and/or the review and analysis of previous reports made available. Prensa notes that sampling is representative only and that due to the lack of homogeneity of building materials it is possible that sampling has not detected all asbestos within the nominated locations.

Given that a representative sampling program has been adopted, not all materials suspected of containing asbestos were sampled and analysed. It is noted that some asbestos materials may have been assumed to contain asbestos based on their similar appearance to previously sampled materials.

Therefore, it is possible that asbestos materials, which may be concealed within inaccessible areas/voids, may not have been located during the investigation. Such areas include, but are not limited to:

- Materials concealed behind structural members and within inaccessible building voids;
- Areas inaccessible without the aid of scaffolding or lifting devices;
- Areas below ground;
- Inaccessible ceiling or wall cavities;
- Areas which require substantial demolition to access;
- Areas beneath floor covering where asbestos-containing materials were not expected to exist;
- Materials contained within plant and not accessible without dismantling the plant; and
- Areas where access is restricted due to locked doors, safety risks, or being occupied at the time of the investigation.

Reliance on Information Provided by Others

Prensa notes that where information has been provided by other parties in order for the works to be undertaken, Prensa cannot guarantee the accuracy or completeness of this information. Victoria Police therefore waives any claim against the company and agrees to indemnify Prensa for any loss, claim or liability arising from inaccuracies or omissions in information provided to Prensa by third parties. No indications were found during our investigations that information contained in this report, as provided to Prensa, is false.

Future Works

During future works at the site, care should be taken when entering or working in any previously inaccessible areas or areas mentioned above and it is imperative that works cease immediately pending further investigation and sampling (if necessary) if any unknown materials are encountered. Therefore, during any refurbishment or demolition works, further investigation, sampling and/or assessment may be required should any suspect or unknown material be observed in previously inaccessible areas or areas not fully inspected, i.e. carpeted floors.